TENDER NO - APS/113/2023-24

CONSTRUCTION OF CORRIDORS/PATHWAYS FOR PREFABRICATED ASSEMBLY HALL AND CLASS ROOMS

SNo	<u>Description</u>	A/U	Qty	<u>Amount</u>
1.	Roof Sheet - Galvin Sheet Support columns	Sqft	5000	
	Truss – Frame truss with 1"/2" x 16 Gage			
	4"MS Round/ Vertical Poles			
	Purling using at every 2.5' Spacing (approx.) 2" Sqr Pipe			
	Roofing with industrial power coated roofing sheet of 0.5mm fixed firmly to purling using self taping screws			
	Measurement roof area 5' x 20' = 100 Sqft Size M/H 10' & 5' x 80' = 400 Sqft Size M/H 10'			
	Total Amount			
	GST			
	Grand Total			